

Village Of Archbold, Ohio
Brush Creek Lift Station Improvements
Contract 2-20

This project will construct a new sanitary lift station, adjacent to South Defiance Street, between Brush Creek and the Archbold Cemetery. This lift station will replace the existing Brush Creek lift station, which was installed in 1970. An existing waterline will be relocated to facilitate construction of the new lift station.

Also included in this project is the relocation of a sanitary sewer that is located near Brush Creek. Past efforts to prevent inflow into this sewer during large rainfall events have proven unsatisfactory. The new 12” sanitary sewer will be rerouted along the north side of the Archbold Cemetery and connect into the proposed lift station. Manhole lids will be installed above the 100-year flood elevation. The existing lift station and the existing sanitary sewer will be abandoned in place.

Preliminary Engineer's Estimate of Construction: \$600,000.00