

**Village of Archbold, Ohio**  
**Miscellaneous Street Resurfacing**  
**Contract 6-20**

This project predominately involves the asphalt street resurfacing of two residential areas. The first area is Buckeye Street with the addition of Storrer Street, Lauber Street, and a portion of DeGroff Avenue. The second resurfacing area encompasses Clover Lane and portions of Murbach Street, Meadow Road, and North Lincoln Street. The streets will be milled (1-3/4") inches deep to allow for a fiber reinforced bituminous membrane surface treatment (Fiber Mat) to be placed below one and a half (1-1/2) inches of asphalt surface course. The Fiber Mat is being installed to reduce reflective cracking. In addition, any concrete curbs in need of repair will be replaced throughout the project limits.

This project will also include the installation of three speed humps in Ruidley Park, a small portion of street resurfacing on West Lutz Road near the Knights of Columbus Hall, and miscellaneous asphalt repairs due to Village related utility construction.

Engineer's Preliminary Estimate of Construction: \$400,000.00