

MISCELLANEOUS SIDEWALK IMPROVEMENTS
CONTRACT 3-20

This project is composed of concrete sidewalk repairs at various locations in the Village of Archbold south of the railroad tracks. The majority of the repairs will be on S. Defiance Street, W. Mechanic Street, W. Barre Road, S. Buehrer Street and Woodland Park. There will also be repairs to sidewalks on a number of other various streets in south Archbold, a driveway repair on E. Lugbill Road, and a curb repair on Charles Street.

The existing concrete walks will be removed and replaced with four inch thick concrete walk to match the existing width. Thicker concrete will be placed at or near driveways or as otherwise necessary.

Engineer's Estimate Of Construction: \$48,000.00